



Automation of Large-Scale Geotextile and Geomembrane Fabrication

Andrew Mills, C.E.T.,¹ Naeem Yassin, M.Eng. E.I.T.²

¹Layfield Canada Ltd., Environmental Containment division, 17720-129 Avenue NW, Edmonton, Alberta, T5V 0C4 Canada; e-mail: Andrew.Mills@layfieldgroup.com

²Layfield Group Limited, 11120 Silversmith Place, Richmond, British Columbia, V7A 5E4 Canada; e-mail: Naeem.Yassin@layfieldgroup.com

ABSTRACT

The fabrication of geotextiles and geomembranes offers advantages in deployment speed and quality over field-installed materials. Traditional fabrication methods have joined one strip of material at a time to create extended panels. Recently, the authors have completed the development of a new fabrication machine that joins five strips of material at a time to create fabricated panels for large projects. The new machine is capable of both welding geomembranes and sewing of high strength geotextiles. This machine was specifically designed to address the problems of scale that need to be dealt with in oil sands tailings ponds. This paper will outline the development of this unique machine and present two case histories; one using high strength sewn geotextile, and one using welded geomembrane. The paper also highlights some exciting new equipment technology and innovation developed specifically for meeting the containment needs of larger scale projects.

BACKGROUND

The development of the large-scale fabrication machine was conceived during the fabrication of geotextiles for a tailing pond cap in 2010. This tailings pond covered was for Suncor Energy Inc and was located in Fort McMurray Alberta. The first phase of the project completed in 2010 required the sewing of 1,300,000 m² of high strength geotextile. This was a unique sludge pond cap that was placed on the ice of the frozen tailings pond and remained floating between years of construction. Details of this first phase of production and installation on the frozen pond were presented at the 2011 Canadian Geotechnical conference (Mills 2011). The project continued for three years and eventually consumed 3.5 million m² of sewn fabric. A second tailing pond cap of a similar size was planned to follow shortly after this pond cap was completed.



Figure 1. Sewing with rail mounted machine. **Figure 2.** 160 x 22.5 m 5-wide panels.

The scale of this fabrication required a large commitment of sewing resources. Fabrication was completed in Edmonton using sewing machines mounted on rails (Figure 1). The geotextile was unrolled in stacks 5 deep in the fabrication bay and then lifted into the sewing machine for joining. Limited length sections of the panel were sewn at a time and then the entire panel advanced by the winder so that the next section could be sewn. This step-wise sewing continued until the entire length of each roll was sewn. Finished rolls were wound up at the same 5.4 m width as the input rolls (Figure 2).

Sewing the geotextile for this project was not challenging from a technical standpoint but was very challenging from scale and capacity standpoint. With the expectation that a second tailing pond cap would follow the first there was motivation to develop a more automated method of manufacture.



Figure 3. Sewing frame with 4 machines.

The first attempt at automating manufacture was an internal effort. Four sewing machines were mounted to a frame and rigged up to sew at the same time (Figure 4). While the coordination of the sewing machines worked well there were problems feeding the geotextile.

There wasn't enough pulling force to pull the fabric through the sewing machines. At this point a search was undertaken to find a specialist in the automation of sewing equipment.

SPECIFYING THE EQUIPMENT

Finding a specialist in automated multi-width fabrication equipment was not difficult. There are some very good automated equipment providers in the US and China that can automate the welding of fabricated geomembranes to most widths. What was more difficult to find was a supplier that could automate the sewing process. After a lengthy search a number of companies specializing in automated sewing equipment were found and the discussions began.

Creating the specifications for the fabrication line started with a review of all fabricated materials. A list was created showing all the fabrics that would likely be sewn on this machine with the required stitch type, thread, and seam strength required. The width and roll diameters of the input rolls were also looked at closely. A summary of the specifications for materials for sewing is shown in Table 1.

	Strength	Weight	Width	Stitch Types
Highest Value	200 kN/m Woven	1000 g/m ² Nonwoven	5.4 m	Butterfly, J, Flat
Lowest Value	20 kN/m Woven	50 g/m ² Nonwoven	1.8 m	J, Flat

Table 1. Specifications for sewn materials.

It is important to note that sewing of high strength woven geotextiles is very specialized and it is difficult to sew fabrics that have cross directional strengths over 100 kN/m. The basic specification for this machine was to sew the highest strength woven geotextiles available.

Although sewing was the main driving force behind the specifications on this machine the reality was that fabrication of geotextiles would not completely fill the capacity of a machine like this in the future. To that end it was decided to add geomembrane welding to the machine's specifications. Another review was completed of all the geomembrane materials that would likely be fabricated paying special attention to the roll widths of materials and the weights/thicknesses. Specifications for welding are summarized in Table 2.

	Width	Thickness
Unsupported (U) Max Value	5.33 m	1.5 mm
Unsupported (U) Min Value	1.5 m	0.5 mm
Supported (S) Max Value	5.33 m	2.3 mm
Supported (S) Min Value	1.5 m	0.3 mm

Table 2. Specifications for welded materials

BUILDING THE LINE

In June of 2010 a request for proposals was sent out to interested vendors. Some initial quotes and concepts were received and reviewed. In the fall of 2010 meetings were set up to discuss the proposals that looked promising. A successful vendor was selected and a contract was awarded the summer of 2011.

The successful concept was that the machine would consist of a large conveyor belt where the stack of material would travel. The initial width was for 5 rolls wide with each roll a maximum of 5.5 m wide. A series of unwind-stands unroll material down onto this conveyor belt to create a stack of material up to 5 high. Sewing machines would be mounted on alternate sides of the conveyor and the welders would be opposite the sewing machines. Sewing would use the sewing machines that were right-left-right-left in the direction of travel and welding would use welding machines that were left-right-left-right in the direction of travel. The unwind-stands and conveyor belt transfer would be common to both methods of fabrication. The right side of the machine in the direction of travel would be the “zero” side with a fixed position. The left side of the machine is adjustable in width with welding/sewing machines and unwind-stands all adjustable to the width of materials.



Figure 4. Assembly of sewing machine.

Design, modification, and building of the machine continued through to the spring of 2014 (Figure 4) with handover trials taking place that summer (Figure 5). Between the time the machine was ordered in 2011 and the time it was delivered in 2014 a new building had been constructed in Edmonton with space reserved for this machine. The new building was fitted with an overhead crane for moving the roll handling frames. That machine was shipped in 14 containers and was installed in the fall of 2014. Acceptance trials followed and handover occurred in November.

The final step in the installation was the naming of the machine. It is now known by the tradename GeoFab 5XTM; however, in this paper it will be referred to as the fabrication machine.



Figure 5. Ready for acceptance trials in 2014.

SUNCOR TAILINGS POND CAP

The 2010 Suncor Tailings pond cap required 3.5 million m² of a high strength woven geotextile. The textile selected was a woven polypropylene provided by Ten Cate with a tensile strength of 105 kN/m in the machine direction and 155 kN/m in the cross machine direction. The specification for the seams on this project were a wide width tensile seam strength requirement of 82.5 kN/m minimum. There were two main components of the cap; the first being 13 km of roads that were 100 m wide; the second being panels to fill the spaces between the roads (called polders) that were typically 300 x 160 m each. Panels were made 22.5 m wide and either 100 m or 160 m long as needed.

The selection of the geotextile, the development of sewing to meet specification, and the development of ice deployment and testing techniques to fulfill the requirements of that project are contained in the paper “A case history on the use of high strength woven geotextiles to reinforce an oil sands tailings pond closure” (Mills 2011). A picture of the finished cap is shown in Figure 6 and a detail of the placement of the fabricated geotextile on the ice is in Figure 7.



Figure 6. Roads and polders on tailings pond.



Figure 7. Fabric placement on ice.

The fabrication of the geotextiles was accomplished using rail mounted sewing machines as shown in Figure 1. Over 600 km of shop seams were required to fabricate this material. The project required 1,353 sewn panels which were completed over a 3-year period.

In 2014 the fabrication machine had just completed acceptance trials when another order came from Suncor for an additional 90 panels for the polder sections of the same pond. This was 326,000 m² of high strength fabric to the same specification that the fabrication machine had been designed for so this was an excellent starting point. The sewing of these panels started at the end of 2014.

Initial qualification seams on the fabrication machine went well however once all four sewing machines were running a number of teething problems became apparent. There did not appear to be any major faults but a collection of small issues had to each be resolved in order for sewing to progress smoothly. To make sure that all materials shipped to site met specifications panels were unrolled and inspected on the floor if there were any issues during the sewing. A camera system was added to show the underside of all sewn seams which allowed the operator to find, mark and repair any skipped stitches (Figure 8). A sample from each panel was also destructively tested to ensure that wide width tensile strengths were maintained.



Figure 8. Camera location.



Figure 9. Smooth sewing.

In January of 2015 a sewing expert was brought in to analyze the sewing. In the evaluation there were 3 small items that were not working well. The biggest problem however was one of setup. The sewing machines on the fabrication machine were custom-made units that used a mechanical sewing arrangement very different from the sewing machines used in normal fabrication. The operators were used to setting up machines which were mechanically very different. With the faults fixed and setup issues resolved the fabrication machine ran smoothly for the balance of the order (Figure 9).

Fabrication of this high strength woven geotextile on the fabrication machine is significantly faster than standard fabrication. When comparing the fabrication rates of the 2010 order with the 2014 order fabrication machine sewed the materials 7.5 times faster on average. At the end of the 2014 order the fabrication machine was sewing at a rate nearly 10 times faster than the 2010 order.

The completion of the 2014 order marks the readiness of the fabrication machine for sewing projects as all major sewing issues were resolved. Sewing projects completed since this time have gone smoothly.

OTTAWA TRAIL ROAD LANDFILL CAP

The second case history is a welded geomembrane cap for the Ottawa landfill completed in 2007/2008. The areas covered were identified as stage 3 and stage 4 of the landfill. The cap was an interim exposed cap. The material used for the cap was a 0.75 mm fortified polyolefin material (Enviro Liner 6030) supplied to fabrication in rolls 3.76 m wide. The 2007 cap required 320,000 m² of material. The material was fabricated into two panel sizes. The first panels were 11 x 70 m and there were 136 of these made. The second panel size was 51 x 40 m and there were 38 of those panels made.

The selection of the geomembrane, a discussion of the ballasting, drainage, and gas venting designs, and a description of the construction are contained in the paper “Innovative design and construction of a landfill cap; a case study of Ottawa’s Trail Road landfill” (Simpson et al 2009). A picture of the layout of the fabricated panels is shown in Figure 10 and an aerial view of the project under construction is in Figure 11.

The fabrication in 2007/2008 was completed using self-propelled wedge welders to weld one seam at a time. Two welding plants were utilized. The 11 x 70 m panels were fabricated in Edmonton and the 51 x 40 m panels were fabricated in Vaughan (near Toronto).

Then in 2015 another section of the Ottawa Trail Road landfill was marked for final closure. The material selected for this final cap material was a 40 mil LLDPE textured on both sides. The new project was 83,000 m² and would be run on the new fabrication machine. The panel sizes chosen were 15.5 m x 122 m each or about 44 panels.




Figure 10. Layout of fabricated panels.



Figure 11. Aerial view under construction.

At the same time as the fabrication machine was being built another division of the author’s company installed an extrusion line to manufacture wide width (7 m) geomembranes. One of the specifications for that line was to make materials to fabricate on the fabrication line. The extrusion line was built with the option to make materials at a special width of 5.33 m to

accommodate the fabrication machine. A brief period of trials (Figure 12) established that a 5.28 width would work best for both the new extrusion line and the fabrication machine. The 40 mil textured material used on the second Ottawa project was 5.28 m wide for the 15.5 x 122 m panels which made them 3-wide (Figure 13).

Working through the details of welding on the fabrication line required that issues be found and resolved. With a machine the size and complexity of the fabrication line it takes time to work out the procedures that will control welding. One aspect that really helped the welding was the design of the welders. The custom wedge welders on the fabrication machine are large, sturdy machines which is something that is only possible on stationary equipment. The wedges have 2,800 watts of heat each which is significantly more than the 1,600 watts of the self-propelled welders used in the rest of the shop. On weld startup the fabrication machine welders do not lose significant temperature and hold their set point very well.

A number of quality control techniques also helped to make sure that all the welds made met the specifications of the project. The first was an infra-red weld inspection system that was installed on the fabrication machine. This special system uses infra-red cameras to measure the temperature of a weld after it has been welded to make sure that there is sufficient heat in the weld to make a seam. If the weld temperatures are not correct an alarm alerts the operator. The second special quality control addition was to use split wedges so that seams could be air pressure tested after welding. The third aspect of quality testing was to perform destructive tests at the end of each roll fabricated.



Figure 12. 5.28 m wide geomembrane.



Figure 13. 15.5 x 122 m panel

Fabrication of the geomembrane for the second Ottawa landfill project was faster than the regular fabrication of the first project. The panels fabricated in Edmonton in 2007/2008 and the panels made on the fabrication machine in 2015 were both three-wide panels. The fabrication rate in 2015 was 4 times faster than the 2007/2008 rate. If the fabrication machine had been able to make 5-wide panels the fabrication rates would have gotten closer to the values seen on the sewing example. The completion of the 2015 order marks the readiness of the fabrication machine for welding projects as all major welding issues were resolved.

CONCLUSION

This paper highlights some innovative new equipment technology and automation developed for the fabrication of geomembranes and geotextiles. The development of a specialized sewing and welding machine to address the scope requirements of large projects has been successfully implemented. While not suitable for smaller projects the increase in fabrication rate is important for speeding the work on larger projects. In the case histories presented the fabrication machine showed a fabrication rate increase of 7.5 times faster than previous methods for sewing and a welding increase of about 4 times faster than previous methods. Significantly faster improvements in welding would be available for 4 and 5-wide welded panels.

A new fabrication machine has been developed that can weld or sew materials with input roll widths of 5.4 m and join them into panels up to five wide at rates up to 7.5 times faster than standard fabrication methods.

REFERENCES

- Simpson, M. Benson, A. Derrick, U. (2009). "Innovative Design and Construction of a Landfill Cap; A Case Study of the City of Ottawa's Trail Road Landfill." *Proc., Geosynthetics 2009*, IFAI, 1801 County Road B W, Roseville, MN.
- Mills, A. (2011). "A Case History on the use of High Strength Woven Geotextiles to Reinforce an Oil Sands Tailings Pond Closure." *Proc., 2011 Pan-Am CGS Geotechnical Conference*, CGS, 8828 Pigott Rd, Richmond BC.